## RFP B2112, Labelle ES School Roof Replacement, Phase 2 Questions and Answers

#	Vendor (contact &	Subject	Question	Response
1.	company) Sam Sheasby Integrated Building Services		Do you have cost estimates for Campbell Middle and Labelle?	Approximately \$800,000
2.	John Larimer  – Larimer  Shannon  Group		Is Johns Manville Tricor product approved for this project?	Yes the Johns Mansfield TriCor product is included as an approved system in the project specifications for Labelle ES.
3.	Melissa Sanders – East Coast Drainage Systems		The primary and overflow drains are separated by a bar joist. Instead of a dual drain plate, can separate drains be installed instead?	Yes.
4.	Robert Klein – Klein Contracting		The first picture shows a transit (asbestos material) exhaust stack on area G 3. Is this to be removed and replaced or are we to flash to transit material?	For the purpose of this bid, assume that it remains in place and will be flashed. If a contractor encounters asbestos at the area to perform work, they need to inform us immediately and CCSD will have it removed.
5.	"		The second set of pictures show conduits running across the roof and with the new roof installation f they will not have the 8" flashing height. How should this be handled?	The conduits in question should be raised and placed on appropriate supports per the construction documents.
6.	"		When will we be receiving the low voltage control allowance as referenced on the drawings?	This reference (Note 17 from Sheet A101) in the next addendum.
7.				