

**Cobb County School District**

RFQ Q2021005, Siding Replacement on NCHS Baseball Press Box

		Vendor Name:	Atlas Construction, Inc.	Stephen R Coomes dba Coomes Maintenance	Graphite Construction LLC	The Macallan Group, LLC dba Macallan Works
		Terms:	Net 30	Net 30	Net 30	Net 30
		Earliest Start Date:	mid September 2020	9/7/20	9/7/20	9/14/20
#	Description		Turnkey Price	Turnkey Price	Turnkey Price	Turnkey Price
<b>1</b>	<p><b>Option 1 – Vinyl (turnkey solution)</b></p> <ul style="list-style-type: none"> <li>* Secure all utilities connected to press box.</li> <li>* Remove existing vinyl fascia/soffit/siding/window trim/skirt from building (approx. 25’x40’).</li> <li>* Inspect siding underneath for damage or rotted sections, replace as necessary.</li> <li>* Wrap structure with suitable weather barrier.</li> <li>* Install new fascia/soffit/siding/window trim/skirt to building.</li> <li>* Caulk all gaps, butt joints, window trim, and other areas as necessary.</li> <li>* Pressure wash and Paint</li> <li>* Permits and inspections.</li> <li>* Removal of debris.</li> </ul>		\$27,250.00	\$6,400.00	\$16,840.00	\$13,969.00
<b>2</b>	<p><b>Option 2 – Cementitious Siding (turnkey solution)</b></p> <ul style="list-style-type: none"> <li>* Secure all utilities connected to press box.</li> <li>* Remove existing vinyl fascia/soffit/siding/window trim/skirt from building (approx. 25’x40’).</li> <li>* Inspect siding underneath for damage or rotted sections, replace as necessary.</li> <li>* Wrap structure with suitable weather barrier.</li> <li>* Install new fascia/soffit/siding/window trim/skirt to building.</li> <li>* Caulk all gaps, butt joints, window trim, and other areas as necessary.</li> <li>* Pressure wash and Paint</li> <li>* Permits and inspections.</li> <li>* Removal of debris.</li> </ul>		\$29,500.00	\$8,400.00	\$18,240.00	\$15,126.00